



Notes:

1. ALL DIMENSIONS ARE IN MILLIMETERS.
2. PROVIDE EXPANSION JOINTS @ 4250mm MAXIMUM SPACING; SEE SPECIFICATIONS.
3. CURBS SHALL BE WOOD OR STEEL FORMED.
4. GENERAL CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH PLAYGROUND INSTALLER.
5. CONCRETE FOOTINGS AND POSTS OF ALL PLAY EQUIPMENT SHALL BE INSTALLED PRIOR TO THE INSTALLATION OF WOOD FIBRE AND AFTER THE SUBGRADE ELEVATIONS ARE ESTABLISHED.