



Notes:

1. ALL DIMENSIONS ARE IN MILLIMETERS.
2. ALL PLANT MATERIAL TO CONFORM TO THE CANADIAN NURSERY STOCK STANDARD, LATEST EDITION, PUBLISHED BY THE CANADIAN NURSERY LANDSCAPE ASSOCIATION.
3. ENSURE TREES ARE THOROUGHLY WATERED AT TIME OF PLANTING. CONTINUE WATERING AS REQUIRED TO PROVIDE ADEQUATE MOISTURE TO THE TREE FOR THE DURATION OF THE SPECIFIED MAINTENANCE PERIOD.
4. REMOVE ALL TAGS, TAPES AND WRAPS IMMEDIATELY FOLLOWING FINAL INSPECTION.
5. TREE IS TO BE STAKED IMMEDIATELY FOLLOWING PLANTING. RUBBER HOSE SHALL BE USED AS A COVER OVER #10 GAUGE WIRE TO PROTECT THE TREE BARK FROM DAMAGE. THE RUBBER HOSE SHALL BE CUT TO A SUFFICIENT LENGTH TO LOOSELY ENCIRCLE THE TREE TRUNK. STAKES SHALL BE INSTALLED PLUMB AT A HEIGHT OF 1500mm AND PARALLEL TO PREVAILING WIND PATTERNS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND DISPOSING THE STAKES AND WIRE 12 MONTHS FOLLOWING THE INSTALLATION OF THE TREE.
6. PLANTING SOIL MIXTURE AS PER SPECIFICATION.
7. REFER TO THE STREET TREE PLANTING LAYOUT DETAIL P611 FOR NEW DEVELOPMENTS FOR OFFSETS FROM OTHER ELEMENTS.