



1. ALL DIMENSIONS ARE IN MILLIMETERS.
2. PROVIDE EXPANSION JOINTS @ 6000mm MAXIMUM SPACING.
3. CURBS SHALL BE WOOD OR STEEL FORMED.
4. GENERAL CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH PLAYGROUND INSTALLER.
5. CONCRETE FOOTINGS AND POSTS OF ALL PLAY EQUIPMENT SHALL BE INSTALLED PRIOR TO THE INSTALLATION OF WOOD FIBRE AND AFTER THE SUBGRADE ELEVATIONS ARE ESTABLISHED.
6. PROVIDE LIGHT BROOM FINISH WITH 150mm WIDE TROWEL EDGE WITH GROOVE.