



Notes:

1. ALL DIMENSIONS ARE IN MILLIMETERS.
2. EXPANSION JOINTS TO BE PREFORMED CLOSED CELL POLYEFIN EXPANSION JOINT FILLER WITH REMOVABLE TOP STRIP, 10mm THICK AND SPACED 6000mm ON CENTER TO FULL DEPTH OF CONCRETE SLAB OR AS OTHERWISE SPECIFIED ON PLAN.
3. EXPANSION JOINTS ARE REQUIRED WHERE CONCRETE PAVING ABUTS STRUCTURES.
4. ALL PERPENDICULAR TOOL MARGINS FROM FINISHING TOOL FOR EXPANSION JOINTS ARE TO BE BROOMED OUT SO THAT NONE EXIST.
5. CONTROL JOINTS TO BE CUT 32mm INTO THE SLAB AND SPACED 1500mm ON CENTER MAXIMUM, OR AS OTHERWISE SPECIFIED ON PLAN.
6. FINISHED CONCRETE SURFACE TO BE SLOPED TO A MINIMUM OF 2% WITH A MAXIMUM 3.5% SLOPE AND CONFORM TO THE APPROVED GRADING PLAN. SURFACES THAT ARE SLOPED BELOW 2% ARE TO BE REVIEWED BY THE CITY PRIOR TO APPROVAL AND STAMPED BY A QUALIFIED PROFESSIONAL.
7. ENSURE THAT ALL ORGANIC MATTER IS REMOVED FROM THE EXCAVATED AREA PRIOR TO PLACING AND COMPACTING BASE MATERIAL.
8. CONCRETE TO BE DOWELED INTO ADJACENT, NEW OR EXISTING CONCRETE WITH EPOXY COATED DEFORMED STEEL DOWELS - 15Mx600mm LONG @ 600mm O.C. AT ALL JOINTS.